

# **Light Emission Distribution Laboratory**

Division of Photometry & Electrical Testing Pty. Ltd

Unit 4, 140 George St. Hornsby NSW 2077 Australia

Ph: +61 2 9476 3097 E: sales@ledlab.com.au



## **Test Report: 180701LCP**

# Testing of FloodLight Power for AEMO's NEM Load Table and other tests on optical systems

for iGuzzini EH Maxi Woody 3K Floodlight Model No. EH40.0

Type of LED Floodlight

product:

Prepared for: Illuminotechnica, Unit 20, 43-45 College St, Gladesville NSW 2111 Australia

Model number: EH40.0

Description: iGuzzini EH Maxi Woody 3K Floodlight. Features die cast aluminium alloy body, tempered

sealing glass, aluminium reflector, 3000K LED chips powered from an Osram Optotronic LED

driver (model number OT 60/170-240/1A0 4DIMLT2 E).

#### Test objective and Method

Determination of the luminaire supply operating parameters Voltage, Current, Power and Power Factor when tested at nominal test voltages of 250V. By the method of LEDLab Electrical Parameter Determination and AEMO Unmetered\_Load\_Guideline\_v1\_0.

## Test configuration

The ten luminaires were operated at 25°C ambient temperature in their normal operational orientation at 250VAC, 50Hz, until the monitored luminaire stabilised as defined in IES LM79. Twenty readings were taken ten seconds apart and the average found. The average value is multiplied by the Calibration Correction given in the latest NATA endorsed calibration report then has Voltmeter losses subtracted based on Watt-meter input impedance and test voltage. The other nine luminaires having operated for the same or more time are switched one by one to Watt-meter for their twenty readings.

Client: Illuminotechnica, Unit 20, 43-45 College St, Gladesville NSW 2111 Australia contact Robert Woodward

#### Conclusion

The Average Load (W) is 56.78W at 0.97 Power Factor.

Tested by: David Orwin On 05/07/2018 Authorised Signatory Date: 09/07/2018

Bayla:

Alain Yetendje

## Results

Time till stabilisation: 2h

#### **Electrical Measurements**

Sample 1	Supply Voltage (Vrms)	Input Current (Arms)	Input Power (W) Power Factor
Average	250.347	0.234	56.904 0.972
Min	250.060	0.233	56.884 0.972
Max	250.680	0.234	56.920 0.973
Calibration correction (see Newton 4 <sup>th</sup> calibration report NC17.36115) Instrument impedance correction (N4) Final value	0.9999 250.32	0.9999 0.00024 0.2335	0.9998 1.0000 0.0576 56.84 0.972
Sample 2	Supply Voltage (Vrms)	Input Current (Arms)	Input Power (W) Power Factor
Average	250.067	0.233	56.736 0.974
Min	248.620	0.233	56.719 0.973
Max	250.610	0.234	56.753 0.974
Calibration correction (see Newton 4 <sup>th</sup> calibration report NC17.36115) Instrument impedance correction (N4) Final value	0.9999 250.04	0.9999 0.00024 0.2328	0.9998 1.0000 0.0576 56.67 0.974
Sample 3	Supply Voltage (Vrms)	Input Current (Arms)	Input Power (W) Power Factor
Average	250.380	0.233	56.732 0.974
Min	249.900	0.232	56.713 0.973
Max	250.630	0.233	56.746 0.975
Calibration correction (see Newton 4 <sup>th</sup> calibration report NC17.36115) Instrument impedance correction (N4)	0.9999	0.9999	0.9998 1.0000 0.0576
Final value	250.35	0.2324	56.66 0.974

Sample 4  Average Min Max	Supply Voltage (Vrms) 250.333 249.820 250.980	Input Current (Arms) 0.234 0.233 0.234	Input Power (W) Power Factor 56.995 0.974 56.979 0.974 57.018 0.974
Calibration correction (see Newton 4 <sup>th</sup> calibration report NC17.36115)	0.9999	0.9999	0.9998 1.0000
Instrument impedance correction (N4)		0.00024	0.0576
Final value	250.30	0.2335	56.93 0.974
Sample 5	Supply Voltage (Vrms)	Input Current (Arms)	Input Power (W)
Average	250.462	0.234	56.947 0.973
Min	249.990	0.233	56.926 0.972
Max	250.980	0.234	56.969 0.974
Calibration correction (see Newton 4 <sup>th</sup> calibration report NC17.36115) Instrument impedance correction (N4) Final value	0.9999 250.43	0.9999 0.00024 0.2334	0.9998       1.0000         0.0576       0.973
Sample 6	Supply Voltage (Vrms)	Input Current (Arms)	Input Power (W) Power Factor
Average	250.273	0.233	56.843 0.974
Min	249.660	0.233	56.811 0.973
Max	251.020	0.234	56.866 0.974
Calibration correction (see Newton 4 <sup>th</sup> calibration report NC17.36115)  Instrument impedance correction (N4)	0.9999	0.9999 0.00024	0.9998 1.0000 0.0576
Final value	250.24	0.2330	56.78 0.974

LEDLab Test Report: 180701LCP

	LEDLAO TEST REPORT. 18070TLCP			
Sample 7	Supply Voltage (Vrms)	Input Current (Arms)	Input Power (W) Power Factor	
Average	250.429	0.233	56.730 0.973	
Min	249.050	0.232	56.694 0.972	
Max	251.290	0.234	56.759 0.974	
Calibration correction (see Newton 4 <sup>th</sup> calibration report NC17.36115)  Instrument impedance correction (N4)	0.9999	0.9999 0.00024	0.9998 1.0000 0.0576	
Final value	250.40	0.2325	56.66 0.973	
Sample 8	Supply Voltage (Vrms)	Input Current (Arms)	Input Power (W) Power Factor	
Average	250.267	0.233	56.789 0.973	
Min	249.590	0.233	56.766 0.972	
Max	250.860	0.234	56.810 0.974	
Calibration correction (see Newton 4 <sup>th</sup> calibration report NC17.36115)  Instrument impedance correction (N4)	0.9999	0.9999 0.00024	0.9998 1.0000 0.0576	
Final value	250.24	0.2330	56.72 0.973	
Sample 9	Supply Voltage (Vrms)	Input Current (Arms)	Input Power (W) Power Factor	
Average	250.098	0.240	56.796 0.948	
Min	249.640	0.239	56.768 0.947	
Max	250.950	0.240	56.815 0.948	
Calibration correction (see Newton 4 <sup>th</sup> calibration report NC17.36115) Instrument impedance correction (N4)	0.9999	0.9999 0.00024	0.9998 1.0000 0.0576	
Final value	250.07	0.2394	56.73 0.948	
Sample 10	Supply Voltage (Vrms)	Input Current (Arms)	Input Power (W) Power Factor	
Average	249.975	0.234	56.975 0.974	
Min	249.290	0.234	56.952 0.973	
Max	250.460	0.235	56.996 0.974	
Calibration correction (see Newton 4 <sup>th</sup> calibration report NC17.36115)  Instrument impedance correction (N4)	0.9999	0.9999 0.00024	0.9998 1.0000 0.0576	
Final value	249.94	0.2338	56.91 0.974	

#### Electrical operating parameters of iGuzzini EH Maxi Woody 3K Floodlight

Sample No.	Supply Voltage (Vrms)	Input Current (Arms)	Input Power (W)	Power Factor
Sample 1	250.347	0.233	56.836	0.972
Sample 2	250.036	0.233	56.669	0.974
Sample 3	250.349	0.232	56.664	0.974
Sample 4	250.302	0.233	56.928	0.974
Sample 5	250.430	0.233	56.880	0.973
Sample 6	250.242	0.233	56.775	0.974
Sample 7	250.398	0.233	56.662	0.973
Sample 8	250.236	0.233	56.722	0.973
Sample 9	250.067	0.239	56.729	0.948
Sample 10	249.943	0.234	56.907	0.974
Average	250.23	0.23	56.78	0.97

Illustration 1: Electrical operating parameters of iGuzzini EH Maxi Woody 3K Floodlight

#### **Uncertainties**

At a Confidence Level of 95% with a Coverage Factor of 2

Supply Voltage:± 0.07% Supply Current:± 0.14% Supply Power:± 0.19% Power Factor:± 0.005 Ambient Temperature:± 1°C

## Test Equipment Used

Power meter: Newton 4th Power Analyser KinetiQ Model PPA2520 SN 133-00467

*Power meter integration time (s):* 5

Calibration Report: Ausgrid NC17.36115

Luminaire thermometer: AMA S No. 1086110-0.1deg

## **General Photographs**




Illustration 2: Luminaire label



Illustration 3: LED driver



Illustration 4: Luminaire



Illustration 6: Optical opening



Illustration 5: Setup